


LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
CHIPPEWA CO. 2 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> N. R. <u>6</u> E.		<u>E-5, F-5</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ S., R. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S., R. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		


 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-29, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-5 S.W. Section Corner of Section 9. OBT'S: Cedar 8", N58°E, 16 lks. & Birch 8", S42°W, 6 lks.
 F-5 South 1/4 Corner of Section 9. OBT'S: Cedar 8", N20°E, 17 lks. & Cedar 8", N14°W, 63 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-5 Corner set by single proportionate measure between original Meander Corner East side of Vanio Lake 1348.50' West and Section Corner 1 mile East. I feel this is proper position for this corner rather than using double proportionate measure.
 F-5 Corner set midpoint on line between S.W. Corner and S.E. Corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monuments set at both corners.

- | | |
|-------------------------------|----------------------------|
| E-5 16" W. Pine, S63°E, 39.2' | F-5 10" Cedar, S88°W, 4.9' |
| 10" Cedar, N64°E, 29.7' | 12" Cedar, N18°W, 34.8' |
| 18" W. Pine, S75°W, 82.0' | 10" Cedar, N67°E, 15.1' |
| 8" Spruce, N52°W, 51.4' | 10" Cedar, S10°E, 30.4' |

SIGNED BY Gerald L. Wiggins DATE 6-14-89


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET