

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHIPPEWA

(County)

Located In:

Corner Code *→*

1. Public Land Survey	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
2. Property Controlling in Section	S	<u>6</u>	T	<u>41N</u>	R	<u>6E</u>	_____	<u>8</u>
	S	<u>6</u>	T	<u>41N</u>	R	<u>6E</u>	_____	<u>11</u>
3. Miscellaneous	S	_____	T	_____	R	_____	_____	_____
Property in Sec.	S	_____	T	_____	R	_____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	15	16	17	18	19	20	21	22	23	24	25	26	27
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Gerald L. Wiggins, in a field survey on 9-6, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 8 Established the West 1/16 Corner of Section 6.
 11 Established the S.W. 1/16 Corner of Section 6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 8 Corner set by single proportionate measure between West 1/4 Corner and Center Corner of Section 6.
 11 Corner set at intersection of West 1/16 Line and South 1/16 Line of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR MONUMENTS SET AT BOTH CORNERS.

- | | |
|---|--|
| 8 6" Cedar, S40°W, 12.7' | 11 22" Spruce, N25°E, 32.45' |
| 7" Cedar, West, 11.7' | 12" Cedar, S26°W, 53.7' |
| 5" Cedar, N49°E, 8.7' | 16" Cedar, S52°W, 48.4' |
| 8" Cedar, S08°E, 3.9' | 10" Cedar, S79°W, 13.9' |
| Iron W/L.S. Cap #27450, N80 1/2°E, 74.99' | Iron W/L.S. Cap #27450, N84°E, 125.83' |

Signed by

Gerald L. Wiggins

Date 10-10-89

Surveyor's Michigan License No. 23521

