

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

CHIPPEWA

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	<u>41N</u>	R	<u>6E</u>	<u>D-3</u>		
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S	<u>5</u>	T	<u>41N</u>	R	<u>6E</u>	<u>11</u>
	S	<u>5</u>	T	<u>41N</u>	R	<u>6E</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gerald L. Wiggins, in a field survey on 9-6, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 D-3 South 1/4 Corner of Section 5. Set by myself on 5-19-87.

11 S.W. 1/16 Corner of Section 5. Not previously set.

12 West 1/16 Corner of Section 5. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 D-3 Corner was set wrong on 5-19-87. Moved 9-6-89

11 Corner set at center of S.W. 1/4 of section 5 by closed traverse.

12 Corner set midpoint on line between South 1/4 Corner and computed Center of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**DNR MONUMENTS PLACED AT ALL THREE CORNERS.**

D-3	7" Cedar, N40°W, 51.8'	11	20" R. Pine, N3°E, 26.1'	12	8" Cedar, West, 15.50'
	10" Cedar, N17°E, 27.9'		12" Cedar, N56°E, 12.35'		7" Cedar, N52°W, 21.95'
	7" Cedar, S3°W, 41.2'		12" Cedar, S22°E, 33.7'		6" Cedar, N37°E, 17.15'
	6" Cedar, S72°W, 49.3'		12" Cedar, S69°W, 42.95'		6" Cedar, S15°W, 12.80'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by

*Gerald L. Wiggins*

Date 10-16-89

Surveyor's Michigan License No. 23521

