

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 41 NR 7 E  
T 41 NR 8 E  
T 42 NR 7 E  
T 42 NR 8 E

Drummond Island

Chippewa

COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Sections 1, 6, 31, 36~~

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" brass cap

WITNESSES TO CORNER

10" H. Maple - N 53 E - 24 Links

10" Beech - S 50 W - 48 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. Burned over area, no original evidence at corner.

Corner was placed and witnessed October 6, 1953.

SURVEYORS SEAL

SIGNED John C. [Signature] DATE 1/26/54  
REGISTERED LAND SURVEYOR