

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 41N R 7E	G7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 10/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 15-16-21-22. 1845 - Established by John Mullett, Deputy Surveyor: Set post. Pine 10" N75E 6 links, Pine 10" S67W 10 links. 1953 - Corner remonumented Oct. 5, 1953 by Dean C. DeLaMater RLS, from one original B.T. still in place, in good condition. Mr. DeLaMater placed a 1"ID Iron pipe with 4" brass Michigan Dept. of Conservation cap and the following new bearing trees: 24" W.Pine N87E 41 links, 12" Cedar S32W 28 links. The record describing this corner was prepared Jan 26, 1954.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1953 monument as described, in good condition, and at record bearing and distance from the 1953 NBTs, both in good condition with overgrown blazes. Found no sign of the original BTs. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 24" W.Pine S82E 28.03' mrkd "S22" 1953 NBT
 18" Cedar S44W 19.15' "S21" do
 11" Balsam N65W 6.07' mrkd "S16 NBT"
 12" W.Birch N24W 12.22' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities