

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code ##

1	Public Land Survey		T 42N R 2E	I-9
			T 42N R 2E	G-6
			T R	
			T R	
2	Property Controlling in Section	S 15	T 42N R 2E	3
		S	T R	
3	Miscellaneous Property in Sec	S	T R	
		S	T R	

Register of Deeds Stamp & File Number

4 Lot No. Recorded Plat
 5 Private Claims

I, Gerald L. Wiggins, in a field survey on 4-30 & 6-27 1991
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A Description of original monument and accessories and/or subsequent restoration:

- I-9 Section Corner 22,23,27,26. Set by Billy D. Buckler, R.L.S. on 6-6-79. Cedar, S80°E, 6.35'
 G-6 1/4 Corner between 16 and 15. OBT'S: Cedar 8, N35°E, 10 lks. & Cedar 6", S30°W, 14 lks.
 3 North 1/16 Corner on west side of section 15. Not previously set.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

- I-9 Marked new witnesses at Buckler's DNR Monument.
 G-6 Corner set at a Squared Post on south end of N-S line of fence posts, with no wire. An old
 square cedar tree with 1/4 written on blaze stands to northwest. Fence line runs east and
 beginning of a cut line west. There also is a squared post 66' east on fence line.
 3 Corner set M.P.O.L. between west 1/4 corner and N.W. corner of section 15.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monuments placed at all three corners.

- I-9 10" Cedar, S80°E, 6.35' & 6" Cedar, N22°E, 37.1' & 5" Cedar, N62°E, 25.0' &
 4" Cedar, N41°E, 15.35'.
 G-6 14" Cedar, N53°W, 19.35' & 6" Cedar, N15°W, 8.4' & 6" Cedar, S88°E, 6.9' &
 10" Cedar, S10°E, 11.2'.
 3 12" Oak, N83°E, 18.5' & 12" Oak, S71°E, 25.0' & 8" Maple, S44°E, 14.4' &
 12" Oak, S02°E, 9.3'.

Signed by

Gerald L. Wiggins

Date 7-8-91

Surveyor's Michigan License No.

23521

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

