

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

CHIPPEWA COUNTY

*2 corners*

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> <sup>N.</sup> R. <u>2</u> <sup>E.</sup>	B-II; C-5;
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9/18/74, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners set by John Mullett, D.S. in 1845.

B-II; Quarter Corner bet. Secs' 30-31. Bearings were:

W. Pine 8", S48E, 13 Lks. and Fir 7", N34W, 20 Lks.

C-5; Section Corner, 7-8-17-18. Bearings were:

Cedar 10", N62W, 30 Lks. and Cedar 8", S48E, 17 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-II; Corner replaced from remains of W. Pine Bearing tree.

Stump cut low with Notch and bottom of blaze remaining.

C-5; Corner replaced from remains of both original Bearing trees.

NW Cedar is a stub, 20' high, with both faces good, scribe marks plain; SE Cedar is a stump, 16" high in poor condition, part of bottom face found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe with 4" Alumijum Cap, placed at both Corners.

B-II; New Bearings:

7" Cedar, S64E, 8.4'; 12" Cedar, N13W, 34.0'; 10" Cedar, S79W, 17.4".

C-5; New Bearings:

9" Cedar, N14W, 15.9'; 8" Cedar, S60W, 11.2'; 8" Tamarack, S30E, 28.0'.

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 9/28/76

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1973

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET