

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>X</u> , R. <u>2</u> E. <u>X</u>	M-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 10/28 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
Original Corner placed Sept. 30, 1840 by Wm. A. Burt, D.S. who marked as witnesses Fir 8" S12°W 13 Links and Spruce 10" N50°W 22 Links. Two additional witnesses were marked June 20, 1845 by John Mullett, D.S. a Cedar 12" S36°E 16 Links and Tamarack 10" N47°E 19 Links
Record distance North to Line Tree = 494.3'.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
Found an old dead Cedar Tree, squared at 492' South of a W. Pine Line Tree.
Found old blazes to North, East, and South. Distance checks to stream East; stream and swamp edges to North and stream and swamp edge to West.
Could not positively identify the original witnesses.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
Placed a 1" pipe with 4" aluminum cap and marked new witnesses:

12" Cedar S32°E 46.5'
18" Cedar Stub, N63°E 58.4'

SIGNED BY Billy D. Buckler DATE 10/25/72
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____