

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 2 E.	C-12
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 10/25 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Original $\frac{1}{4}$ Cor. bet. Secs. 31-32, set by John Mullett D.S. on June 27, 1845.

Bearings were:
Cedar 6" S2^oW 75 Links and Tamarack 9" S62^oW 48 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner replaced from Cedar witness. Tree dead but standing. Face is open, with scribe marks very plain. Found bottom of tamarack stump in proper position.

Corner lies in an open, wet marsh. Distance South (2.00 chs) to edge of marsh checks.

This $\frac{1}{4}$ Corner lies 438.8' West of the alignment of the Prentiss Bay Road. This road has been used as the Section Line. Corner found with E. Johnson, Assistant, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap and Cedar post at corner.

New Bearings:
17" Cedar S21^oW 117.5'
13" Cedar S82^oW 94.8'

SIGNED BY Billy D. Buckler DATE 11/27/72
Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____