

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Chippewa Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. Sec. R. <u>2</u> E.	<u>A-5</u> <u>A-6</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 2/8 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- A-5 Sec. Corner bet. 7-18, on West boundary of Township set by Austin Burt, D.S. in 1840.
 Bearings were:
 Fir 5" N23°W 40 lks and Hemlock 10" S27°W 1ks and Cedar 10" N17°E 16 lks.
- A-6 ¼ Corner on Westside Sec. 18, on West boundary of Twp.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- A-5 Found original hemlock witness, a stump, bearing S27°W 35 lks. part of lower face with overgrowth showing scribe marks in evidence.
- A-6 Found 4" Concrete Plat Monument, set by G. F. DeLaMater, R.L.S. in 1947. Found remains of original witness, a W. Pine stump, N8°W, 24 lks, as well as DeLaMaters witness, a W. Pine Stump, S21°W, 31.3'.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- A-5 Piled a mound of stones 2' high at corner, which is located on solid limestone.
 New Bearings:
 W. Pine Stump N2°W 42.4' and 7" W. Birch S37°W 6.4' and W. Birch 7" N14°E 35.7'
- A-6 Placed pile of stones, on east side of corner monument.
 New Bearings:
 24" W. Pine Stump S21°W 32.4' and 22" W. Pine Stump S57°E 24.4' and 24" W. Pine Stump N8°W 16.0'

SIGNED BY Billy D. Buckler DATE 3/5/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)