

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. S., R. <u>2</u> E. W.	A-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1/30 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
 Section corner, 18-19, on west boundary of township, set by Austin Burt, D.S.
 Sept. 28, 1840.
 Bearings were:
 Pine 8" $N22^{\circ}W$ 13 lks. and Pine 5" $S18^{\circ}W$ 7 lks. and
 Pine 6" $S83^{\circ}E$ 19 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
 Found corner, perpetuated by G. F. DeLaMater, R.L.S. in 1947.
 Location is marked by a chiseled cross on a rock; with boulders noted as witnesses, also marked by a chiseled cross.
 Found remains of two of the pine witnesses, still in place.
 DeLaMaters' witnesses are:
 Limestone Boulder 36" wide $N42^{\circ}E$ 19.6'
 Limestone Boulder 72" wide $S25^{\circ}E$ 33.6'
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
 Re-witnessed corner as set by DeLaMater.
 New Bearings:
 8" Cedar $S78^{\circ}W$ 54.3'
 6" Aspen $N9^{\circ}E$ 16.0'

SIGNED BY Billy D. Buckler DATE 3/5/73
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)