

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 2 W.	A-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/28 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Township Corner, originally placed by Austin Burt, D.S., Sept. 28th, 1840.

Bearings were:
Aspen 8" N18¹/₂°W 32 Links
Aspen 6" S25°E 10 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found a 4" Concrete Flat Monument, placed by G.F. DeLa Mater, R.L.S. in 1947.
Found a palmaris tend Tree, blazed on all four sides, 24' East of monument.
This tree blazed 41-43 years ago, determined by count of annual growth rings.
Distance South and East to Lake Huron checks with records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Re-witnessed this corner, as set by Mr. DeLaMater.

Bearings:
11" W. Pine N45°E 5.5'
12" W. Pine N58°W 9.4'
8" Soft Maple S27°W 42.7'

SIGNED BY: Billy D. Buckler DATE: 9/13/72
BILLY D. BUCKLER
SURVEYOR'S MICHIGAN REGISTRATION NO. 837 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY: _____ DATE: _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.