

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

4 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER F-7, E-7, H-7, G-7
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>2</u> E. R. <u>2</u> E.	_____
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-1, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners set by John Mullett, D.S. in 1845. Bearings were:

F-7 Quarter Corner bet. Sec's. 16-21. Spruce 8, N27°W, 6 lks. & Cedar 7, S13°E, 5 lks.

E-7 Sec. Cor. 16-17-20-21. Cedar 6, N17°W, 7 lks. & Tam. 8, S44°E, 11 lks.

H-7 Quarter Corner bet. Sec's. 15-22. Tam. 10, N39°E, 12 lks. & Tam. 8, S43°W, 17 lks.

G-7 Sec. Cor. 15-16-21-22. Spruce 8, N48°E, 14 lks. & Spruce 6, S71°W, 19 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-7 Re-established corner midway and on line bet. Sec. Cors. Stream to East Checks.

E-7 Re-established corner by double proportionate measure.

H-7 Corner re-established midway and on line bet. two section corners.

G-7 Re-established corner by double prop. measure from corners in four directions. Found a wood post 165.8' East of corner. Corner lies 5.0' North of a fence wire.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Buried 1" pipe with 4" aluminium cap at corner. All others placed 1" pipe with 4" Dep't cap.

F-7 8" Cedar, S41°W, 8.7' & 8" Cedar, S51°E, 26.6' & 10" Cedar, N17°W, 18.3'.

E-7 7" Cedar, S15°E, 15.5' & 6" Cedar, S77°W, 17.5' & 4" Cedar, N10°E, 11.4'.

H-7 12" W. Pine, S8°E, 63.0' & 8" Oak, S40°E, 47.5' & 10" Spruce, S89°W, 25.8'.

G-7 6" Cedar, S51°W, 9.1' & 6" Cedar, S72°E, 8.5' & 6" Cedar, N38°W, 8.9'.

SIGNED BY _____ DATE 3-26-80

Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

