

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. 2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>2</u> E. <u>W.</u>	<u>M-7, M-10</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-15, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-7** Section Corner between 13-24, on East bndry. of township, set by Wm. Austin Burt, D.S. in Sept. 30, 1840. Bearings were: Tamarack 5, for corner and Tam. 6, N2°W, 26 lks.
- M-10** Quarter corner on East side of sec. 25, on East township boundary set by Wm Austin Burt, D.S. in 1840. Bearings were: Cedar 8, N67°W, 4 lks. & Cedar 10, S47°W, 24 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-7** Monumented corner in intersection of an old road grade to North and East. This road grade built during the early 1940's.
- M-10** Restored corner by single proportionate measure along the range line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminum cap at both corners. New Bearings:
- M-7** No witnesses available.
- M-10** 8" Red Maple, West, 2.5' & 8" Y. Birch, S66°E, 12.3' & 8" Y. Birch, S1°W, 37.1'. corner placed in old N-S read.

SIGNED BY Billy D. Buckler DATE 3-26-80
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____