

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chipewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. 2 R. 2 E.	E-3, F-3
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-7, 1969, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corners set by John Mullett, D.S. in 1845. Bearings were:

E-3 Sec. Cor. common to Sec's. 4-5-8-9. Birch 10", N20°E, 8 lks. & Cedar 10", S35°W, 28 lks.

F-3 1/4 Cor. bet. Sec's. 4-9. Tamarack 8", S47°E, 6 lks. & Cedar 6", N12°E, 28 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

E-3 This corner placed in E-W road and 3.0' East of a fence corner. Found no evidence of original corner but found an old stake South of road. Distance West agrees with record = 5296.0'.

F-3 This corner placed midway bet. Sec. Cors. and in center of E-W road. Found old blazes and location poster on a down cedary on North side of road.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" x 36" Iron Pipe buried in center of road (E-W), at both corners. Bearings are:

E-3 8" Hemlock, N24°E, 72.8'. & 7" Soft Maple, S47°W, 22.5'.

F-3 8" Tamarack, N24°E, 29.0' & 10" Cedar, N20°W, 33.7'.



SIGNED BY Billy D. Buckler DATE 8-3-81  
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_