

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa
(County)

Located In:

Corner Code //

- | | | | | | |
|---|------------------------------------|---------------|------------|----|--|
| 1 | Public Land Survey | T | R | | |
| | | T | R | | |
| | | T | R | | |
| | | T | R | | |
| 2 | Property Controlling
in Section | S 23 | T 42N R 2E | 13 | |
| | | S 23 | T 42N R 2E | 14 | |
| 3 | Miscellaneous
Property in Sec | S | T R | | |
| | | S | T R | | |
| 4 | Lot No | Recorded Plat | | | |
| 5 | Private Claims | | | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	19	20	21	22	23	24	25	26	27	28	29	30
7													
8	18	19	20	21	22	23	24	25	26	27	28	29	30
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, **Gerald L. Wiggins**, in a field survey on **7-12-90**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- 13 S.E. 1/16 Corner of Section 23. Not previously set.
- 14 South 1/16 Corner on east side of Section 23. Corner set by Billy D. Buckler R.L.S. in 1980.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

- 13 Corner set at center of S.E. 1/4 of Section 23 by closed traverse.
- 14 Moved corner as set by Billy D. Buckler L.S. in 1980 to midpoint on line between East 1/4 corner and S.E. Corner of Section 23.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner


- 13 DNR Monument: 5" Twin Balsam, S18°E, 24.7' & 4" Twin Maple, S60°E, 28.7' & 8" Maple, S84°E, 13.3' & 10" Aspen, N23°E, 20.9'.
- 14 DNR Monument: 7" Cedar, N64°W, 3.3' & 8" Cedar, S81°W, 20.9' & 8" Cedar, S15°W, 6.1' & 7" Cedar, S20°E, 19.0'.

Signed by

Gerald L. Wiggins

Date 9-13-90

Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 26 1971
 REVISED MAY 14 1976
 REVISED JAN 1983