

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHIPPEWA
(County)

Located in:

Corner Code #/

1. Public Land Survey	T 42N R 2E	H-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 15 T 42N R 2E	5
	S 15 T 42N R 2E	8
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **Keith Sackett**, in a field survey on 8-14, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 H-6 Center of Section 15. Not previously set.

- 5 North 1/16 Corner of Section 15. Not previously set.
- 8 West 1/16 Corner of Section 15. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-6 Corner set at intersection of North-South and East-West 1/4 lines of Section 15.
- 5 Corner set midpoint on line between North 1/4 Corner and Center Corner of Section 15.
- 8 Corner placed midpoint of line between West 1/4 Corner and Center Corner of Section 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument placed at all three corners.

H-6 Clump 6" Maples, S54°E, 9.5'	5 12" R. Pine, S85°W, 25.5'	8 10" Beech, S17°W, 10.0'
5" Maple, S60°W, 14.9'	12" R. Pine, N70°W, 24.8'	12" Maple, N72°W, 22.3'
5" Maple, N70°W, 17.4'	6" Spruce, S50°E, 20.25'	8" Maple, N63°E, 7.9'
5" Maple, N11°W, 8.0'	8" Spruce, N68°E, 18.25'	14" Oak, S80°E, 16.6'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

Keith Sackett

Date

10-7-91

Surveyor's Michigan License No. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983