

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>CHIPPEWA</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 15 T 42N R 2E	16
	S 15 T 42N R 2E	13
3. Miscellaneous Property in Sec	S 15 T 42N R 2E	11
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. Recorded Plat  
 5 Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on 8-13 & 8-14, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

- 16 East 1/16 Corner between Sections 15 and 22. Not previously set.
- 13 South-East 1/16 Corner of Section 15. Not previously set.
- 11 South-West 1/16 Corner of Section 15. Not previously set.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 16 Corner placed midpoint on line between South 1/4 Corner and S.E. Section Corner of Section 15.
- 13 Corner set at the intersection of East 1/16 line and South 1/16 line of Section 15.
- 11 Corner set at intersection of West 1/16 line and South 1/16 line of Section 15.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 D.N.R. Monument set at all three corners.

16	8" Twin Oaks, N20°E, 11.65'	13	Twin 5" Maple, S46°W, 27.7'	11	6" Cedar, S78°W, 19.2'
	8" Oak, N75°E, 31.45'		5" Beech, N69°E, 35.1'		12" Cedar, N07°E, 38.0'
	14" Oak, S04°E, 13.9'		12" Oak, N17°E, 34.05'		12" Cedar, N32°E, 22.5'
	8" Oak, N48°W, 19.65'		6" Maple, N05°W, 7.75'		10" Cedar, N08°W, 5.2'

Signed by

*Keith Sackett*

Date 10-7-91

Surveyor's Michigan License No 19006

