

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|------------|---|-----------|-------------------------|-------|
| 1. Public Land Survey | T | <u>42N</u> | R | <u>2E</u> | <u>A4</u> | |
| | T | <u>42N</u> | R | <u>1E</u> | <u>MA (same corner)</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 10 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A4) Quarter corner common to Section 7 T42N-R02E and Section 12 T42N-R01E. 1840 - Established by Austin Burt, Deputy Surveyor: South on East side of Section 12 ...40.00 Set qr. Section post. Birch 14 N29W 19 links, Fir 6 S46W 14 links. ...80.00 Fir 4 corner of Sections 12 and 13. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement, midway and on line between monumented Section corners 2637.87' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 6" Spruce S41W 48.6' mrkd "1/4S NBT"
 6" Spruce S63W 70.35' do
 8" Spruce N43W 84.15' do
 10" Spruce S70E 19.9' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski

Date 1/10/06

Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources

