

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>2E</u>	<u>A8</u>
	T <u>42N</u> R <u>1E</u>	<u>MB (same corner)</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 31 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A8) Quarter corner common to Section 19 T42N-R02E and Section 24 T42N-R01E. 1840 - Established by Austin Burt, Deputy Surveyor. Bearing trees were: Pine 8 N49W 26 links, Pine 6 S22W 20 links. 1947 - notes of a survey by G.F.DeLaMater show this corner was monumented as a part of his survey. 1981 - Record of Billy D. Buckler RLS states: Found 4" concrete monument, set by G.F.DeLaMater, RLS, in 1947. Found original Pine BT in place, N49W 26 links, other Pine BT down. Bearings: Boulder 4' high Southwest 12.0', Boulder 2' high East 6.0', Boulder 2' high North 3.0', Cor. on a side hill, facing to SW.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A8) Found and accepted a 1/2" dia. rebar encased in a 4" dia. concrete cylinder in accord with the 1981 witnesses of record. Found additional witness trees tagged by Ronald Bischer, RLS, not of record. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A8) Fd. 1/2" rebar in a 4" dia. conc. cylinder. Set measuring nails in:
 7" Balsam N53E 6.5' mrkd "1/4S NBT"
 6" Balsam N49W 53.4' do
 6" Maple N41E 18.05' do
 10" B.Spruce S65W 65.4' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski

Date 1/10/06

Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources

