

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa

(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey	T <u>42N</u> R <u>2E</u>	<u>C5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 05 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Corner common to Sections 7-8-17-18. 1845 - Established by John Mullett, Deputy Surveyor. Set post at corner. Witnesses: Cedar 10 N62W 30 links, Cedar 8 S48E 17 links. 1974 - record by Billy D. Buckler, RLS states: Corner replaced from remains of both original Bearing trees. NW Cedar is a stub, 20' high, with both faces good, scribe marks plain; SE Cedar is a stump, 16" high in poor condition, part of bottom face found. Set 1" pipe with 4" aluminum cap. New bearing trees: 9" Cedar N14W 15.9', 8" Cedar S60W 11.2', 8" Tamarack S30E 28.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) Found a 1" ID iron pipe with 4" aluminum MDNR cap, unmarked and not in accord with the 1974 witness trees, all recovered, nor with the stump remains of the original bearing trees. It appears that the monument was moved by someone for reasons unknown. Removed the recovered monument and re-monumented the corner at record bearing and distance from the 1974 witness trees of record. The two cedars are in good condition, the tamarack is dead. Marked two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) Set 1" ID x 36" I. pipe with 4" alum. MDNR cap. Set measuring nails in:  
 10" Cedar N04W 16.0' mrkd "S7 NBT" \*  
 10" Cedar S61W 11.25' mrkd "S18 NBT" \*  
 4" Cedar S19E 12.25' mrkd "S17 NBT"  
 6" Cedar S85E 27.0' mrkd "S17 NBT"  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1974 NBT with 1974 markings found.



Signed by Stephan J. Szyszkoski Date 1/10/06

Surveyor's Michigan License No. 33986  
 For the Michigan Department of Natural Resources