

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>42N</u> R <u>2E</u>	<u>4</u>
	S <u>7</u> T <u>42N</u> R <u>2E</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

7 Aug 31 2005  
 4 Aug 30 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(4-Sec. 19) Northwest 1/16 corner, Section 19. Not established in the original survey. 2000: Monumented by Ronald Bischer RLS at a position "based on section breakdown by Billy Buckler while working for DNR". Survey project number 46-00. Mr. Bischer placed "rod and cap" at the corner. Mr. Buckler's survey, which was in fact not a section breakdown, but rather a survey of the exterior boundaries of the section, was conducted ca. 1974.  
 (7-Sec. 7) North 1/16 corner between Sections 7 and 8. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(4-Sec. 19) Discovered that the 1974 determination of the exterior boundaries of Section 19 by Mr. Buckler is erroneous. Consequently, Mr. Bischer's survey of the SW1/4 of the NW1/4 of Section 19, which was based on field work of Mr. Buckler, is erroneous. I remeasured Section 19 and properly subdivided it, establishing this corner at the intersection of straight lines connecting opposite 1/16 corners. From the corner thus established, I found Mr. Bischer's rod and cap N09E (magnetic) 24.09' distant.  
 (7-Sec. 7) Found and accepted a 1/2" iron rod with plastic cap stamped "RLS 11357", properly established. Left the monument in place and made witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(4) Set 1" IDx36" I. pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Balsam N74W 4.55' mrkd "NW1/16 BT" 5" W. Birch S08E 9.07' do 8" W. Birch N59E 12.7' do 4" Balsam S40E 3.55' do Bearings are magnetic. Distances are to nail with tag.	(7) Found 1/2" iron bar with plastic cap #11367. Set measuring nails in: 6" Birch S72W 40.75' mrkd "N1/16 BT" 11" Balsam N87W 36.15' do 12" Balsam N61W 32.35' do 10" Balsam S45E 13.4' do Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski Date 1/10/06  
 Surveyor's Michigan License No. 33986  
 For the Michigan Department of Natural Resources

