

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: _____ Corner Code ~~≠~~ _____

1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>42N</u> R <u>2E</u>	<u>16</u>
	S <u>19</u> T <u>42N</u> R <u>2E</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 30 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 19) East 1/16 corner between Sections 19 and 30. Not established in the original survey.
 (8-Sec. 19) West 1/16 corner, Section 19. Not established in the original survey. 2000: monumented by Ronald Bischer RLS at a position "based on section breakdown by Billy Buckler while working for DNR". Survey project number 46-00. Mr. Bischer placed "rod and cap" at the corner. Mr. Buckler's survey, which was in fact not a section breakdown, but rather a survey of the exterior boundaries of the section, was conducted ca. 1974.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 19) Established the corner midway and on the Section line between monumented Section and Quarter corners 1326.38' east and west.
 (8-Sec. 19) Discovered that the 1974 determination of the exterior boundaries of Section 19 by Mr. Buckler is erroneous. Consequently, Mr. Bischer's survey of the SW1/4 of the NW1/4 of Section 19, which was based on field work of Mr. Buckler, is erroneous. I remeasured Section 19 and properly subdivided it, establishing this corner 20 chains, proportionate to the parenthetical original record, west of the Center of Section 19 and on a straight line with the West 1/4 corner. Distance west to 1/4 corner is 1437.39'. Distance east to Center of Section (unmonumented) is 1317.50'. From the corner thus established, I found Mr. Bischer's rod and cap N09W (magnetic) 24.86' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 3" Balsam N50W 5.35' 3" Balsam S02E 18.2' 3" Balsam S55W 2.85' 3" Balsam N47E 12.72' The trees are marked with a small unscribed upper blaze only. Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Tamarack N16W 15.0' mrd "W1/16 8T" 6" W.Birch N60E 17.3' do 10" Spruce S64E 37.85' do 4" Spruce N72W 14.6' do Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski Date 1/10/06
 Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources

