

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 42N R 2E	G4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 42N R 2E	16
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 16 09/02/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G4) Quarter corner common to Sections 9 and 10. 1998 - Reestablished by Ronald R. Bischer RLS and recorded in Book 10 of LCRC, Page 281. Set 1/2" rod by single proportion. N61E 31.2' fence corner, S61E 28.1' gate post, N79W 43.4' fence corner, North 2637.48' 1/2" pipe.

(16-Sec. 9) East 1/16 corner between Sections 9 and 16. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G4) Found a 1/2" rebar at substantial record bearing and distance from the 'gate post' witness S61E 28.1' and at record distance from a 1/2" rebar North 2637.44' M (rec. 2637.48') at the Section corner common to 3-4-9-10. The Fence corner N79W was found down on the ground at substantial record bearing and distance. The monument was found S22E 0.26' from a position midway and on line between Section corners and I accept same as a careful and faithful reestablishment of the position of the original corner.

(16-Sec. 9) Established the corner midway and on the Section line between Section corner 1333.37' east and Quarter corner 1333.37' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G4) Fd. 1/2" rebar  
 Gate post S54E 28.1' to fd. nail/Chippewa Co. tag  
 Set measuring nail with MDNR tag in the side of:  
 Gate post N50E 32.1'  
 8" Scotch Pine S76W 46.3' mrkd "1/4S NBT"  
 10" Scotch Pine N35W 96.8' do  
 Bearings are magnetic.

(16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 9" Maple S03E 5.55' mrkd "E1/16 BT"  
 10" Cedar N84W 13.7' do  
 12" Oak N49E 8.25' do  
 10" W.Birch N89E 18.55' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/15/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

