

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 9 T 42N R 2E _____	3
	S 9 T 42N R 2E _____	4
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 08/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(3-Sec. 9) North 1/16 corner between Sections 8 and 9. Not established in the original survey.

(4-Sec. 9) Northwest 1/16 corner, Section 9. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(3-Sec. 9) Established the corner midway and on the Section line between Section corner 1324.89' north and Quarter corner 1324.89' south.

(4-Sec. 9) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |   |
|--|---|
| <p>(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br/>         11" Balsam N72E 20.5' mrkd "N1/16 BT"<br/>         12" Balsam N48E 32.5' do<br/>         12" Balsam N13E 52.55' do<br/>         10" Spruce S47W 80.85' do<br/>         Bearings are magnetic.</p> | <p>(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set measuring nail with MDNR tag in the side of:<br/>         10" twin Sugar S85E 3.45' mrkd "NW1/16 BT"<br/>         9" Balsam S10E 45.1' do<br/>         8" Sugar S86W 23.5' do<br/>         8" Sugar N14W 40.5' do<br/>         Bearings are magnetic.</p> |
|--|---|

Signed by Stephan J. Szyszkoski Date 10/15/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

