

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 2E	G3
	T 42N R 2E	G5
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on G3 08/31/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1988 - Previously recorded in Liber 7, Page 089 by Gerald A. Myers RLS. Found 1/2" iron at intersection of roads 1.5' north of Centerline of Traynor Road at surface of pavement. Telephone Pole N45E 46.16' to P.K., Telephone Pole S44E 45.85' to P.K., Power Pole S64W 40.34' to P.K.

(G5) Corner common to Sections 9-10-15-16. 1983 - William L. Karr RLS record in Liber 6 of LCRC Page 031 states: Corner is 1" iron pipe 2' east of centerline of Springer Road. Witnesses: 8" S.Maple S45E 54.53', Triple 8" S.Maple S75E 16.80', Twin 18" R.Oak S54W 66.85', 16" Oak Stump (NBT) N58W 34.60'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Found the 1/2" rebar of record 8" below the pavement and at substantial record bearing and distance from the Power pole witness S64W 40.34'. The two telephone pole witnesses are gone. Placed a 1/2"x8" capped rebar above the monument to raise it to the surface of the pavement.

(G5) Found a 1" ID Iron pipe in good condition and at substantial record bearing and distance from three of the four 1983 witnesses, in good condition. The fourth 1983 witness, the 16" Oak stump, is now gone. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Set 1/2"x8" rebar with plastic MDNR cap above found 1/2" dia. rebar.
 Power Pole 'GTI 8174' S64W 40.55' P.K. nail
 Set nail with MDNR tag in the side of:
 14" R.Pine S30E 50.45' no blazes made
 9" Scotch Pine N40W 52.55' do
 7" R.Pine N66E 70.0' do
 Bearings are magnetic.

(G5) Found 1" ID Iron pipe.
 Set measuring nail with MDNR tag in the side of:
 13" triple Sugar S68E 17.3' mrkd "S15" 1983 NBT
 20" Oak S60W 66.85' "S16" do
 14" Sugar S31E 54.7' "S15"
 Anchor Pole N22W 59.6'
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/15/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

