

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 2E	I11
	T 42N R 2E	I10
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on I11 05/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I11) Corner common to Sections 26-27-34-35. 1979 - Reestablished by Billy D. Buckler RLS by double proportionate measurement from "corners in four directions". Set 1" pipe with 4" aluminum cap. 8" Cedar N35E 5.0', 6" Cedar S85W 35.9', 10" Cedar S43E 26.3'.

(I10) Quarter corner common to Sections 26-27. 1979 - Reestablished by Billy D. Buckler RLS midway and on line between two Section corners. Set 1" pipe with 4" alum. cap. 10" Cedar N44E 26.5', 10" Cedar N72W 21.1', 6" Cedar S10W 17.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I11) Recovered the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses, all in good condition. Left the monument in place and made new witnesses as described below.

(I10) Recovered the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses. Verified the position of the monument as being 0.2' east and 8.8' south of the position midway and on a straight line between Sections corners I9 and I11 and I accept same as the reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" twin Cedar N35E 5.3' mrkd "S26" (1979 NBT)
 14" Cedar S40E 26.7' "S35" do
 12" Cedar S88W 36.2' "S34" do
 11" Cedar N18W 26.45' mrkd "S27 NBT"
 Bearings are magnetic.

(I10) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Cedar N07E 9.65' mrkd "1/4S NBT"
 12" Cedar N46E 26.85' mrkd "1/4S" (1979 NBT)
 14" Cedar N69W 21.7' open blazes do
 8" Cedar S09W 17.45' mrkd "1/4S" do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/16/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

