

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 42N R 2E	K11
	T 42N R 2E	K9
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on K11 05/20/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K11) Corner common to Sections 25-26-35-36. 1979 - Reestablished by Billy D. Buckler RLS "from corners in all four directions. Found no evidence of original corner". Set 1" pipe with 4" aluminum cap. 4" W.Birch S53W 10.9', 8" Aspen N04E 31.4', 8" Aspen S13E 38.1'.

(K9) Corner common to Sections 23-24-25-26. 1979 - Reestablished by Billy D. Buckler RLS by double proportionate measurement between corners 1 mile North, 1 mile East, 1 mile West, and 2 miles South. Corner lies in Beaver pond, 75' north of high ground. Set 1" pipe with 4" aluminum cap. 8" Spruce S39E 37.6', 10" S.Maple S7W 47.3', 16" Balm-of-Gilead S68W 21.8'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K11) Found the 1979 monument in good condition and at record bearing and distance from the 1979 NBTs. The Aspen NBTs are in good condition. The W.Birch NBT is dead. Left the monument in place and made new witnesses as described below.

(K9) Found the 1979 monument in good condition, in a beaver pond 48' north of high ground, at record bearing and distance from the S.Maple NBT, standing dead, and the Spruce NBT, tipped over. The Balm-of-Gilead NBT was not recovered. Left the monument in place and made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 14" Aspen S17E 38.4' mrkd "S36" 1979 NBT  
 16" Aspen N15E 31.5' "S25" do  
 6" Birch S84E 6.45' mrkd "S36 NBT"  
 5" Birch S82W 25.1' "S35 NBT"  
 Bearings are magnetic.

(K9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" Maple S51E 61.55' mrkd "S25 NBT"  
 8" Balsam S17E 68.75' do  
 7" Balsam S02E 59.9' do  
 12" Maple S09W 47.5' "S26 NBT"  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/16/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

