

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 2E	J11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 26 T 42N R 2E	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on J11 07/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J11) Quarter corner common to Sections 26 and 35. 1979 - Reestablished by Billy D. Buckler RLS midway and on line between two section corners. Set 1" pipe with 4" aluminum cap. 8" W.Birch N18W 9.4', 6" W.Birch S26W 9.7', 6" W.Birch S62E 26.7'.

(2-Sec. 26) East 1/16 corner between Sections 23 and 26. 1979 - Established by Billy D. Buckler midway between Quarter corner to west and Section corner to east. Set 1" ID I.pipe with 4" aluminum cap. 7" Aspen N66W 3.4', 14" Spruce S71E 33.5', 8" Spruce S43E 20.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J11) Found the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses. The W.Birch NW and the W.Birch SW are in good condition. The W.Birch SE is dead. Verified the position of the monument as being 0.4' south and 4.1' west of the position midway and on a straight line between Section corners east and west and I accept the monument as the reestablishment of the position of the original corner.

(2-Sec. 26) Recovered the 1979 monument disturbed but in good condition N14E 57' from the position of record, it apparently having been moved by persons unknown. Removed the monument and reinstalled it at the record position, in accord with the record bearing trees, said position being substantially at the midway position between Quarter and Section corners. Note that the record distances to the Spruce BTs in the SE were transposed on the 1979 record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J11) Fd. 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Maple N78W 12.4' mrkd "1/4S NBT"
 8" Maple S44E 18.1' do
 11" W.Birch N14W 9.96' old blazes 1979 NBT
 9" W.Birch S28W 9.87' do do
 Bearings are magnetic.

(2) Reset 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Spruce S67E 20.88' mrkd "E1/16" 1979 BT
 17" Spruce S40E 34.42' do do
 6" Spruce S27W 13.71' mrkd "E1/16 BT"
 6" Spruce N03E 17.87' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/16/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

