

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 2E	J9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 26 T 42N R 2E	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on J9 07/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(J9) Quarter corner common to Sections 23 and 26. 1979 - Reestablished by Billy D. Buckler RLS midway and on line between two Section corners. Set 1"ID I.pipe with 4" aluminum cap. 5" R.Pine N31E 15.0', 6" R.Pine N29W 15.8', 6" R.Pine S35W 24.1'.

(14-Sec. 26) South 1/16 between Sections 25 and 26. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J9) Found the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses, all in good condition. Verified the position of the monument as being 3.4' south and 2.2' west of the position midway and on line between Section corners and accepted same as the reestablishment of the position of the original corner.

(14-Sec. 26) Established the corner midway and on the Section line between Quarter corner 1323.03' north and Section corner 1323.03' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" R.Pine N34E 14.96' mrkd "1/4S" 1979 NBT  
 11" R.Pine N28W 15.88' do do  
 11" R.Pine S39W 24.2' do do  
 12" R.Pine N59W 9.71' mrkd "1/4S NBT"  
 Bearings are magnetic.

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" W.Birch N70E 63.8' mrkd "S1/16 BT"  
 11" Tamarack N49E 45.17' do  
 No other trees near.  
 Corner lies in Westerly edge of beaver pond.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/16/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities