

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR. 5 E

Chippewa COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 30-31

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" Cedar N 60° E 19 links

"1/4 S NBT"

5" Cedar S 16° E 44 links

"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner.

Found old cedar stake on ground. Old squared tree and several blazes facing this stake.

Road built N-S 30 links east of corner. Old fence line from east to this 1/4 Corner.

Numerous cedar stumps in area, all badly burned, rotted and scared. Distance east to small lake checks good. No positive evidence of B.T.s.

1/4 Corner lies 30 links west of old road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/28/57  
REGISTERED LAND SURVEYOR