

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 42 NR 5 E

Chippewa COUNTY
Drummond Island

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 29-30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	7" Cedar	N 40° E	15 links
	6" Cedar	"1/4 S NBT"	27 links
		S 19° W	
		"1/4 S NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner.

Found very old cedar post. No evidence of original B.T.s. Distance south to section corner in lake checks short about 60 links for 1/2 mile.

Found old stone fence about 10 chs. east of post which appears to line up with post. Checks very good for bearings north and south to corners.

Post accepted as 1/4 corner for purpose of subdivision of Sec. 29.

1/4 corner lies in swamp.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/20/57
REGISTERED LAND SURVEYOR