

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 42 .. NR .. 5 E ..

Chippewa

Drummond Island

COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 20-29

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" Aspen S 5° W 67 links

"1/4 S NBT"

7" Aspen N 17° E 12 links

"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by proportionate measure and on line between section corner 19-20-29-30 and meander corner between Sec.'s 20-29.

No evidence of original corner or B.T.s.

1/4 corner lies 2 chs. south of road.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6/20/57