

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 .. NR. .. 5 E ..

----- Chippewa ----- COUNTY
----- Drummond Island -----

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 19-20 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 7" W. Pine ----- N 71° W ----- 58 links -----
"1/4 S NBT"

6" Aspen ----- N 4° W ----- 44 links -----
"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by Gov't chainage from Section Corner 1/2 mile south and on line between Section Corner 19-20-29-30 and meander corner between 19-20.

No evidence of original corner or B.T.s.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 6/20/57
REGISTERED LAND SURVEYOR