

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T ~~41-42~~ NR 5 E

Chippewa COUNTY
Drummond Island

DESCRIPTION OF CORNER 1" pipe with 4" brass cap

DESCRIPTION OF CORNER MONUMENT Section Corner common to Sec.'s 4-5-32-33

WITNESSES TO CORNER	<u>5" Cedar</u>	<u>N 42° E</u>	<u>119 links</u>
	<u>6" Aspen</u>	<u>*S 33 NBT° S 62° W</u>	<u>18½ links</u>
	<u>6" W. Birch</u>	<u>S 10° E</u>	<u>51 links</u>

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from two white pine B.T.s bearing N 84° E 39 links in poor condition, badly burned and N 25° W 27 links in fair condition.

Bearing blaze, notch and parts of scribe marks visible.

No evidence of use.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/19/57
REGISTERED LAND SURVEYOR