

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR. 5 E.

Chippewa COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 19-20-29-30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>5" Red Oak</u>	<u>S 25° W</u>	<u>106 links</u>
		<u>"S 30 NBT"</u>	
	<u>6" Aspen</u>	<u>N 51° W</u>	<u>39 links</u>
		<u>"S 19 NBT"</u>	
	<u>6" Aspen</u>	<u>N 89° E</u>	<u>30 links</u>
		<u>"S 20 NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by proportionate measure between meander corners east and west on Lake Huron and from wood post $\frac{1}{2}$ mile south which is accepted as $\frac{1}{4}$ corner between Sec.'s 29-30.

Found old fence about 10 chs. west of corner which appears to be a line of occupation.

Placed location pester $\frac{1}{2}$ chs. south on road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/19/57
REGISTERED LAND SURVEYOR