

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.42 N NR .5 E . .

--- Chippewa --- COUNTY
Drummond Island

DESCRIPTION OF CORNER Meander corner between Sec.'s 19-30 on shore of Lake Huron.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>3" W. Birch</u>	<u>N 45° E</u>	<u>48 links</u>
		<u>"NBT"</u>	
	<u>3" W. Birch</u>	<u>S 10° E</u>	<u>53 links</u>
		<u>"NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found 1/2" iron bar and wood post set by unknown surveyor. No evidence of original corner or B.T.s.

Found by Forestry Division Survey Crew.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/23/57
REGISTERED LAND SURVEYOR