

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42.. NR. 6. E..

----- Chippewa ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between sections 17 & 18 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 4" Cedar - S 50 E - 11 Links -----

12" Cedar - N 21 E - 39 Links -----

5" Cedar - S 53 E - 44 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division Survey crew, while making a survey in this area. This North and South line was cut through from the section corner 1/2 mile South, to the lake shore. The lakeshore was meandered in both directions to prove our position. A hard fire has burned this area, but one probable B.T., a Tamarack, is still in place, badly burned.

Corner was placed and witnessed October 4, 1950.

SURVEYORS SEAL

SIGNED James C. DeLoe DATE 12/27/50
REGISTERED LAND SURVEYOR