

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
Chippewa Co. Drummond Is.      3 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>X</u> , R. <u>6</u> E. <u>X</u>	<u>G-5 /</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>42</u> N. <u>X</u> , R. <u>6</u> E. <u>X</u>	<u>7A-Sec.16 /</u> <u>2-Sec.16 /</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10/15, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

G-5      Section Corner 9-10-15-16.  
7A-Sec.16      Meander corner on North side Potagmising Bay, and on Eastside Section 16.  
2-Sec.16      East 1/16 Corner on Northside, Section 16.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

G-5      Replaced Corner at post, with a pile of stone. Corner set by F.H. Brown, CO. Surveyor, in 1909. Found Brown's records at Co. Courthouse.  
7A-Sec.16      Placed corner at record distance (728.0') South of Sec. Cor. 9-10-15-16, and in old fence line.  
2-Sec.16      Placed corner at old fence corner, being 1,316.8' West of Sec. Cor. 9-10-15-16.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminum cap at all corners.  
G-5      New Bearings: 30" W. Pine Stump, N10°E, 27.7'  
7A-Sec.16      Bearings: None Available  
2-Sec.16      Bearings: None Available

SIGNED BY Billy D. Buckler      DATE 1/17/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_