

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa  
 (County)

Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>6E</u> <u>K1</u>
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Nov 22 1999

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (K1) Corner common to Sections 1-2 T42N-R06E and 35-36 T43N-R06E. 1956: Remonumented by Billy D. Buckler RLS: "Replaced Section corner from one White Pine (probable) 8.T. Distance East 80.25 chs. to good corner". Mr. Buckler placed 1" pipe with 4" brass cap and marked the following: 8" Tamarack S85W 22 links, 7" Cedar S40E 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (K1) Found the 1956 monument, a 1" ID iron pipe with 4" brass MI Dept. of Conservation tablet, in good condition, and at substantial record bearing and distance from the 1956 Cedar NBT in good condition, and from the stump remains of the 1956 Tamarack. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K1) Found 1" ID iron pipe with 4" brass cap. Blazed, scribed, and set measuring nails in:  
 12" Cedar S32E 12.50' "S2" \*  
 14" R.Pine S59W 12.95' "S1 NBT"  
 6" Balsam N60E 18.35' "S36 NBT"  
 16" R.Pine S14W 31.40' "S1 NBT"  
 Bearings are magnetic. Distances are to nail with tag set this date. \* denotes 1956 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/27/03