

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 2 East.

Chippewa COUNTY  
Drummond Island

DESCRIPTION OF CORNER 1/4 corner for sections 21 - 22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 5-13-58

10" hard maple N 72°, E 43 1/2 links. Marked "SNET"

15" hard maple S 67°, W 25 links. Marked "SNET"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced from two sugar bearing trees, bearing N 30°, E 29 links. Tree cut, found old scars and overgrowth with scribe marks. Also bearing S 46°, W 37 links. Tree down and rotted, old scars evident. Corner placed with W. Lehman, District Forester, P. Milligan, Hardwood and T. Bailey, Drummond Island. Corner lies in old logging road.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 6-17-59  
REGISTERED LAND SURVEYOR