

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHIPPEWA

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	<u>42N</u>	R	<u>7E</u>	M.C. bet. <u>I-9&I-10</u>
	T	<u>42N</u>	R	<u>7E</u>	<u>I-11</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 9-7, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M.C. Bet. I-9 & I-10. Corner was set by Billy D. Buckler, R.L.S. on 5-14-58. 1" Iron Pipe at Corner with 8" Cedar, N36°E, 30 links and 5" Balsam, S53°W, 22 1/2 links.

I-11 Section Corner for sec's. 26-27-34-35. Corner was set by Billy D. Buckler R.L.S. on 5-14-58. 1" pipe with 4" brass cap at the corner with 3" White Birch, N33°E, 45 links and 16" Cedar Stump S40°W, 97 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M.C. Bet I-9 & I-10. Re-witnessed this corner as set by Buckler.

I-11 Re-witnessed this corner as set by Buckler.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M.C. Bet. I-9 & I-10. Re-marked the top blazes on Buckler's 1958 trees which are still standing and marked two more witness trees: 5" Cedar, West, 13.4' and 6" Balsam, S57°E, 41.3'.

I-11 Buckler's 3" White Birch is now a 7" and still standing the Cedar Stump is out of the ground. Marked three new witness trees: 7" Aspen, S48°W, 15.5' & 7" W. Birch, S69°E, 33.2" & 6" W. Birch, N77°E, 34.2'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by Gerald L. Wiggins
 Surveyor's Michigan License No. 23521

Date 2-26-90

