

JAN 18 2001

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

SECTION

LAND CORNER RECORDATION CERTIFICATE

93 DEC 29 PM 2:48

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 43N R 2E B-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

J. Roger Matthe
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William L. Karr, in a field survey on December 7, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-1) North 1/4 Corner of Section 6 (T43N-R2E)
Corner not established in original survey.

1963: Neal Sperhake, L.S. 7876 (Kimberly Clark Corp.). Witness Corner recorded in Liber 3, Page 122 of the Chippewa County Corner Records.

Re-established corner position midway between the Northwest and Northeast corners of Section 6 and held centerline of Gogomain Road for North-South position. Set a 1" pipe with stamped aluminum cap as a Witness Corner 33.02' South. Witnessed the Witness Corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a PK nail. Found the recorded Witness Monument 33.02' South of the PK nail. Ronald R. Bischer, L.S. 22428, has placed nails and L.S. tags in the side of witness objects in the area. Also found a railroad spike 19.99' to the East (South 1/4 Corner of Section 31). Distance East to the Northeast corner of Section 6 is 2622.11 (Sperhake - 2624.16'). Distance West to the Northwest corner of Section 6 is 2625.95' (Sperhake - 2625.16'). Accepted corner position as found and offset it prior to road reconstruction. Replaced corner after construction completed. Added two additional witnesses.

Note: Corner falls 0.15' North of the Township Line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-1) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Corner falls in centerline of Gogomain Road (East-West, paved). Falls 20' West of the centerline of West Bay Road to the North (North-South, gravel)

Witnesses:

- Anchor Pole N62°E 62.64' (existing nail & L.S. 22428 tag)
- 14" White Birch S22°E 67.66' (existing nail-no tag, Common Witness)
- 1 1/4" O.D. Pipe with Stamped South 33.02'
- Aluminum Cap
- 8" Ash S45°W 104.80'
- 6" Balsam Fir N32°W 65.92'
- South 1/4 Corner Section 31 East 19.99'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983