

JAN 18 2001

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE 93 DEC 29 PM 2:50  
Filing Requirement of Act 74, Mich. P.A. 1970

*J. Roger Malotte*  
REGISTER OF DEEDS

SECTION

For corners in  
Chippewa  
(County)

Located In: Corner Code #

1. Public Land Survey	T 43N R 2E	H-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-1) North 1/4 Corner of Section 3 (T43N-R2E)  
Corner not established in original survey.

1963: Neal Sperhake established this corner midway between the Northeast and Northwest corners of Section 3. Set a 1" galvanized iron pipe with stamped aluminum cap (Kimberly Clark) as a witness corner 33' South of the 1/4 Corner position with one witness to the Witness Corner.  
Maple 4 S23°E 47 1/2 links.  
Witness corner was recorded in Liber 3, Page 114 of the Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-1) This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found the Witness Corner. Re-established corner position 33.00' North (right angle to a straight line between the Southwest and Southeast corners of Section 34) of the found Witness Corner. Distance East to the Northeast corner of Section 3 is 2630.59' (Sperhake - 2636.70'). Distance West to the Northwest corner of Section 3 is 2636.69' (Sperhake - 2636.70').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-1) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Falls 2' North of the centerline of Gogmain Road (East-West, paved).

Witnesses:

4" Spruce	S22°E	48.60'
1 1/2" Pipe with Stamped Aluminum Cap	South	33.00'
12" Balsam Fir	S14°W	49.33'
11" Spruce	N07°W	56.52'
South 1/2 Corner Section 34	East	42.24'



Signed by William L. Karr Date 12/23/93  
27450

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1970  
REVISED MAY 14, 1970  
REVISED JAN. 1971

