

JAN 18 2001

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPWEA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 PM 2:51

J. Roger Malott
REGISTER OF DEEDS

For corners in
Chippewa
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>2E</u>	<u>L-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William L. Karr, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(L-1) North 1/4 Corner of Section 1 (T43N-R2E)

Corner was not set in original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(L-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of corner position. Corner was established midway between Closing Corner 2/1 and the Township Corner on the Township Line between the South 1/4 and the Southwest corner of Section 36 (T44N-R2E)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(L-1) Corner is a 3/4" x 8' rod with "Chippewa County" stamped aluminum cap. Corner falls on an East-West brush line.

Witnesses:

5" Tamarack	N26°E	6.90'
3" Tamarack	S23°E	18.80'
4" Tamarack	S75°W	25.07'
4" Tamarack	N35°W	8.88'
South 1/4 Corner Section 36	East	20.97'



Signed by *William L. Karr* Date 12/23/93
Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
REVISED MAY 14, 15
REVISED JAN. 15

