

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Chippewa Co. Three Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. <u>X</u> , R. <u>2</u> E. <u>X</u>	E-10, F-10, G-10
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-7, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners placed by John Mullett, D.S. in 1845.
 E-10 Quarter Corner Bet. Sec's. 28-29. Bearings were: Fir 8", S63°E, 14 lks. and Beech 10", S83°W, 23 lks.
 F-10 Center Corner, Section 28.
 G-10 Quarter Corner bet. Sec's. 27-28. Bearings were: Tamarack 12", S56°W, 25 lks. and Tamarack 6", N11°E, 17 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-10 Placed corner at a wood post, believed set by R. Larsen, R.L.S., 1945.
 F-10 Placed corner at a wood post, set by R. Larsen, R.L.S.
 G-10 Placed corner midway bet. two old fence, on North-South road and on an extension of a strait line thru Center of Section 28.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Dep't. markers at all corners.
 E-10 New Bearings: 28" W. Pine Stump, N59°E, 104.8'
 F-10 New Bearings: 5" Red Pine, S89°W, 46.8' and 18" H. Maple, N17°E, 71.8'
 G-10 New Bearings: 12" Cedar, N85°E, 29.7'

SIGNED BY Billy D. Buckler

DATE 12-17-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____