

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chipnawa Co.

Three Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. X., R. <u>2</u> E. X.	E-9, F-9, G-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-7, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners placed by John Kullett D.S. in 1845.

- E-9 Sec. Cor. 20-21-28-29. Bearings were: Sugar 30", N56°E, 10 lks. and Fir 10", S7°W, 16 lks.
- F-9 Quarter Corner bet. Sec's. 21-28. Bearings were: Sugar 10", N72°E, 10 lks. and Maple 10", S72°W, 21 lks.
- G-9 Sec. Cor. 21-22-27-28. Bearings were: Fir 12", N87°E, 14 lks. and Sugar Sugar 10", S57°W, 10 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9 Found a large Granite Boulder in aprox. road intersection. This boulder does have some magnetic attraction.
- F-9 Placed $\frac{1}{4}$ cor. in East-West road, between two fence corners (65.0') apart.
- G-9 Placed corner in road intersection, as indicated by records in County Surveyor's office, Sault Ste. Marie.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9 Chiseled a cross on buried boulder, at corner.
New Bearings: Fence Corner, N42°E, 37.5' and Fence Corner, S31°W, 34.1' and hard Maple 22", N39°W, 46.7'.
- F-9 Buried a 1" x 18" iron pipe in road.
New Bearings: Fence Corner, North, 32.5' and Fence Corner, South, 32.5'
- G-9 Placed 1" x 14" iron pipe in road intersection.
No Witnesses.

SIGNED BY Billy D. Buckler
Billy D. Buckler

DATE 12-17-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____