

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Chippewa

(County)	Located in:	Corner Code ##
1. Public Land Survey	T 43N R 2E	611
	T 43N R 2E	610
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec	S _____ T _____ R _____	
	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on April 21, 1992, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(611) Corner established by U.S. Deputy Surveyor James H. Mullett, 1845. Witnesses: Birch 8 N95E 17', Birch 8 S75W 6'. Corner appears in County Surveyor fieldbook (presumably F.H. Brown ca. 1910) with the following witnesses: Telephone pole SE 24', Telephone pole NW, Fence corner 31.7' west and 36' north. Monument for corner is not identified. Found no subsequent record.
 (610) Corner previously recorded by Billy D. Buckler in 1975 as a pipe with a Michigan Dept. of Natural Resources cap with witness: 12' Cedar N85E, 29.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(611) Original post and accessories not recovered. Brown's witnesses not recovered. Found no monumentation at this position. Used the following as evidence of the location of the original corner: n-s trail along E. line sections 33 and 28, E-W 1/16 line fence in section 34 found by Billy D. Buckler in 1977 1327.8' south, 1/4 bet. 33 and 34 determined by Buckler and monumented by Waters in 1990 2655.17' south, SE corner section 33 recorded by Waters in 1990 5310.61' south, 1/4 bet. 27 and 28 monumented and recorded by Buckler in 1975 2682.56' north, NE corner sec. 28 rec. by Buckler in 1975 5323.45' north. Buckler determined north-south position for 612 and this corner (611) based on location of fence and the corners noted. Specifically, 612 was reestablished 2/3 dist. from 613 to fence and 611 1/3 of that distance north of fence. This resulted in nearly equal 1/2 miles along the east line of sec. 28. I accepted Buckler's position and placed monument for 611 at this latitude and in centerline of north-south trail as with 69 and 612.
 (610) Found and accepted 1" pipe with 4" cast aluminum MDNR tablet and Buckler's cedar BT agreeing. Found three newer witnesses set by unknown surveyor as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(611) Set 1"x32" painted iron pipe with Yellow plastic R.L.S. #33986 cap 6" below gravel surface. N59E 22.72' Set nail and MDNR tag in NW face 12" W. Birch; S49E 21.55' Set nail and MDNR tag in SW face 9" W. Birch; S31W 61.4' Set nail and MDNR tag SE face 11" Tamarack; N54W 36.1' Set nail and MDNR tag NE face B' Spruce. Blazed and scribed all trees at BH and root crown. Bearings magnetic (decl. 7 deg. West)	(610) Found 1" pipe with MDNR tablet. N87E 30.02' Fd. nail in S. face 14" cedar, blazed and scribed (Buckler's BT); S92E 5.18' Fd. nail in E. face 7" cedar; N28E 24.35' Fd. nail on 8" W. Birch; S71W 50.2' Fd nail in 12" Tamarack. All except Buckler's BT were found blazed at BH and root crown, but not scribed. Bearings magnetic (decl. 7 deg. W)
--	---



Signed by Stephan J. Szyszkoski

Date MAY 12, 1992

Surveyor's Michigan License No. 33986