

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Chippewa
 (County)

	Located in:	Corner Code #1
1. Public Land Survey	T 43N R 2E	D9
	T 43N R 2E	C9
	T 43N R 2E	D9
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No. Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

D9 January 28, 1992
 C9 January 29, 1992
 D8 January 27, 1992

I, Stephan J. Szyszkoski, in a field survey on D8 January 27, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D8) Corner not established in original survey. Found no subsequent record.
 (C9) Corner previously recorded by Ostling (LCRC rec. L.1 P. 79, Chippewa County records) as Fd. 2" pipe in 1973.
 (D9) Corner established by John Mullett, 1845. Accessories: Sugar 10 SSW 10, Fir 8 N18W 20. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(D8) Found no monumentation at this position. Established corner at the intersection of straight lines connecting opposite 1/4 corners.
 (C9) Found and accepted 2" pipe. Ostling's 3 accessories check. This corner is being recorded to document additional accessories.
 (D9) Original post and accessories not recovered. No monumentation found at corner location. From the pattern of cultural improvements along the south line of section 20, and the discrepancy in the distance with GLD between the SE corner and SW corner of the section (5400' M, 5293' R), I conclude that the original corner was placed on a random line east from the SW corner and not midway on the corrected line between section corners as stated in the original notes. There is evidence that this situation also exists in relation to the south 1/4 corner of section 29, T43N-R2E. The improvements noted above are: location of the county road along the south line of the section with a pronounced angle point at the corner location, remains of an old E-W fenceline south of and parallel to the road, and the remains of an old N-S wire fence south of the corner location. I reestablished the corner in the road surface and at record distance east from the SW corner of section 20 as recorded this date. My measure east and west to adjacent corners is 2753.53' and 2646.6' respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(D8) Set 1"x32" painted iron pipe with cast aluminum MDNR tablet. N40W 13.50' MDNR tag in SW face 6" maple; N55E 24.62' MDNR tag in SW face 6" maple; S59E 44.30' MDNR tag in NE face 4" maple; S10E 15.40' MDNR tag in NW face 8" maple. Bearings magnetic (decl. 7 deg. W). Trees blazed and scribed at base and BH. Note: blazes face a position 26' east of corner.	(C9) Found 2" iron pipe. S19E 23.75' Stop sign; N40W 36.25' Stop sign; S60W 42.2' MDNR tag in Power pole. Bearings are magnetic (decl. 7 deg. W.)	(D9) Set 1"x32" painted iron pipe with yellow plastic RLS cap below road surface. S36E 64.0' MDNR tag in 38" maple, (blazes face north); S68W 47.0' MDNR tag in 14" maple; N62W 66.8' MDNR tag in 36" maple; N30E 73.9' MDNR tag in SE face 5" oak (blazes face NE). Bearings are magnetic (decl. 7 deg. W). Trees blazed and scribed at base and BH.
---	---	---

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski Date 2-12-1992
 Surveyor's Michigan License No. 33986

