

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

	Located In	Corner Code #/
1. Public Land Survey	T 43N R 2E	CB
	T 43N R 2E	D10
	T R	
2. Property Controlling in Section	T 43N R 2E	5
	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 5 February 11, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	28	27	26	25								
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (CB) Corner established by John Mullett, 1845. Accessories: Fir 12 538W 25, Tank B 549E 15. Corner noted in Aug. 1908 notes of County Surveyor F.H. Brown as follows: "Ref. 1/4 post 1920 W. pine 12 S52W 20'. Put in large cedar post in a dug hole, could not find 1/4 post on east side [i.e. E. side Sec. 19]. I put in post to flatten the bend as much as possible and use as much of the road surface as possible, could not find any old blazes near the random although there was large timber near." Brown's notes show that he placed the 1/4 post midway between section corners north and south.
- (D10) Corner not established in original survey. Corner recorded by Ostling (LCRC rec. L. 1, P. 79, Chippewa County Records) as set 1/2" iron bar in 4" cedar post at intersection of 1/4 lines.
- (5) Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (CB) Original evidence not recovered. Brown's post and W. Pine not recovered. Reestablished corner equidistant and on a straight line between C7 and C9 both as recorded this date. Found remains of old E-W wire fence at corner location. C/L of N-S road is about 60' East of monumented position. Found, but did not accept as reliable evidence, another old wire fence running east into section 20 about 76' south of the monumented position.
- (D10) Found but did not accept corner recorded by Ostling. My measurements show that Ostling's corner was placed not at the intersection of 1/4 lines but rather midway and on a straight line between his recorded D11 and a position near D9 as recorded this date. I established the corner at the intersection of straight lines connecting opposite 1/4 corners using the following: N1/4 corner rec. 1973 by Ostling, North 1/4 and South 1/4 rec. 1992 by Szyszkoski, and E1/4 rec. 1975 by Buckler.
- (5) Established corner equidistant and on a straight line between D7 and D8 both as recorded this date. Old E-W fence line is approx. 80' south of corner. I note that several fence lines existing within the interior of this section are at variance with subdivision lines and I do not regard them as reliable evidence of prior surveys or of the original location of the controlling government corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|---|---|
| (CB) Set 1"x32" painted iron pipe with 4" cast aluminum MDNR tablet. North 0.42' MDNR tag in S. face 10" squared maple; NBOW 40.2' MDNR tag in SW face 12" cedar; N49W 28.0' MDNR tag in NE face 10" N. Birch; SB3E 34.6' MDNR tag in NE face 14" hemlock; East 49' corner location tag nailed on 2" balsam. Bearings magnetic (decl. 7 deg. W.). Trees blazed and scribed at base and BH. | (D10) Set 1"x64" painted iron pipe with cast aluminum MDNR tablet. N25E 120.7' MDNR tag in 12" maple; N59E 144.0' MDNR tag in 8" cedar; N02E 133.9' MDNR tag in 8" maple; S09W 100.3' Found 1/2" iron bar previously recorded. Bearings are magnetic (decl. 7 deg. W.). Trees blazed and scribed at base and BH. Corner falls in beaver pond. Placed squared cedar post adjacent. | (5) Set 1"x32" painted iron pipe with 4" cast aluminum MDNR tablet. N26E 26.10' MDNR tag in E. face 14" maple; N64E 24.32' MDNR tag in W. face 12" oak; S70E 28.65' MDNR tag in NE face 10" oak; S22E 16.05' MDNR tag in NW face 12" oak. Bearings magnetic (decl. 7 deg. W.). Trees blazed and scribed at base and BH. Note: blazes face 205° E of East of corner. |
|--|---|---|

Signed by Stephan J. Szyszkoski Date 2-12-1992
 Surveyor's Michigan License No. 33986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 14, 1975
 LICENSED LAND SURVEYOR
 33986

